

Corrigendum: RFP for “Providing, Fixing & Installing Furniture, Fixtures and AC system for Centralized GoG Call Center” at Karmyogi Bhavan, Gandhinagar on behalf of Department of Science and Technology (P&A 201617/1)

Item no	Description as per the tender clause	Revised description
6	Providing and fixing storage cabinets of 45 cm x75 cmx 90 cm, 45 cm x120 cm x 150cm, 45 cm x 60 cm x210 cm size having 19 mm plywood structure and 12mm plywood shutters with 1.5mm formica or equivalent lamination on front and 2 coats of paint with primer and putty at the inside. Necessary hardware of lock, handle, magnet etc. to be provided as per approved design.	Providing and fixing storage cabinets of 45 cm x75 cmx 90 cm, 45 cm x120 cm x 150cm, 45 cm x 60 cm x210 cm size having 19 mm plywood structure and 19 mm plywood shutters with 1.0 mm lamination on front and back side. Necessary hardware of lock, handle, magnet etc. to be provided as per approved design.
9	Work tables with 1 drawer which would have a steel frame with 19 mm plywood having 1.5 mm laminate on exterior side and oil paint applied with 2 coats of putty and comor on inside - 60cmx120cm measurement of the top having post form.	Work tables with 1 drawer made with 19 mm plywood sides and structure, having 1.0 mm laminate on exterior side and inside of approved ISI brand. 60 cm x 120 cm top having post form MDF with 1 mm thick laminate and .8 mm in edges as may be required.
15	Providing and fixing Gypsum board 8 mm plain color false ceiling with aluminum frame consisting of 600 mm x 600 mm 3mm thick plain gypsum board sheet used as panel inserted in a frame work made using anodized aluminum T section of size 1" x 1" (25 x 25 mm, gauge or 1 mm thick) in square pattern of grid sizes of 2 x 2 (600 x 600 mm). The aluminum frame work is supported from the ceiling with the help of G.I. hook and G.I. wire/6 mm M.S. rods of required size to maintain proper level etc. The aluminum frame work is supported on side wall with the use of aluminum L section of size 1 x 1 (25 x 25 mm) angles etc. Complete s per direction of Engineer in charge. Manufactures, specification and drawing. To be painted with 2 coats of approved brand oil paint with 2 coats of putty and primer	Providing and fixing Gypsum board plain color sound absorbent false ceiling with aluminum frame consisting of 600 mm x 600 mm 8 mm thick perforated approved brand gypsum board sheet used as panel inserted in a frame work made using anodized aluminum T section of size 1" x 1" (25 x 25 mm) 1 mm thick in square pattern of grid sizes of 2 x 2 (600 x 600 mm). The aluminum frame work is supported from the ceiling with the help of G.I. hook and G.I. wire /6 mm M.S. rods of required size to maintain proper level etc. The aluminum frame work is supported on side wall with the use of aluminum L section of size 1" x 1" (25 x 25 mm) angles etc. Complete as per direction of Engineer in charge. Manufactures, specification and drawing. The gypsum board to have 5 cms thick glass wool layer inside as sound absorbent material. Gypsum board to be painted with 2 coats of approved brand oil paint with 2 coats of putty and primer.
		All the MDF top mentioned in number of items (3, 4, 5, 9) to have 1 mm thick laminate on top and .8 mm thick laminate on curved and other type of edges as may be specified.