

Response to Pre-Bid Queries/ Suggestion

Bid for Selection of Agency for Supply, Installation, Commissioning and warranty support of various Equipments for the Implementation of Video Surveillance System at Govt. Industrial Training Institute (ITI) working under Directorate of Employment and Training, Gandhinagar. (Tender No. HWT060120601)

Sr. No.	RFP Reference/Page No./Clause No. /Section No.	RFP Clause / Specifications	Query / Clarification / Suggestions from the Venders	Responses of GIL
1	Page No.18/ARTICLE –34	34.2 50 % of the amount shall be paid within 30 days after Supply, inspection of the items as per work order and successful Installation of goods at all locations 34.3 30 % of the amount shall be paid within 30 days upon successfully clearing the FAT 34.4 20 % of Total Contract Amount will be retained and shall become payable after six months from the date of awarding the FAT on the basis of successful clearance from the competent authority.	Supply, inspection of the items as per work order and successful Installation of goods at all locations & upon successfully clearing the FAT 90% of the Sum total of financial bid. Amount will be retained and shall become payable after six months from the date of awarding the FAT on the basis of successful clearance from the competent authority 10% of the Sum total of financial bid	No Change, As per RFP
2	Page No.18/ARTICLE –33	The work has to be completed within 60 Working days for the date of Work Order issued. The bidder has to take the necessary approval of THE OFFICE for Schematics Diagram (Layout) within 15 working days for cabling & laying work of Video Surveillance System and complete the working from the remaining 45 days.)	Pls. Change From 60 To 90 Working Days.	No Change, As per RFP
3	Additional	Additional	<ul style="list-style-type: none"> As Per RFP Switch BoQ Nos. Of Ports are Not Sufficient for CCTV and Uplink Connectivity. (Each Location Have Only 30 Port For 32 Camera) Suggest to Add 24 Port Switch @ Central Location Where All Other Switches Connect for NVR Need Some Spare Ports To Accommodate Location Wise Camera 	Please See the changes in the Corrigendum
4	Additional	Additional	<ul style="list-style-type: none"> UTP Cable Will Not Fulfill CCTV Networking Requirement 	No Change, As per RFP
5	Additional	Additional	<ul style="list-style-type: none"> Location Wise BoQ Required For All ITI 	The total BoQ is equally distributed in 12 nos. of ITI
6	page No.25 clause 5.3.17/ 08 Port Network Switch	The Switch should be Rack mountable & the switch should be supplied with Indian standard AC power cord, suitable Patch Panels with I/O's	08 Port Network Switch Remove the suitable Patch Panels with I/O's	Please See the changes in the Corrigendum
7	page No.24 clause 5.1.15/ Indoor Fixed Dome Cameras	Indoor Fixed Dome Cameras Camera should support internal/external microphone and 32GB Micro SD/SDHC /SDXC memory card for recording	Camera should have internal/external microphone and 32GB Micro SD/SDHC /SDXC memory card for recording	Please See the changes in the Corrigendum
8	Page No 24/Section 5/ 5.1 Indoor Fixed Dome Cameras	Video Compression: H.264, H. 265	Request to consider & add H.265+ also, which is latest compression technology	Please See the changes in the Corrigendum
9	Page No.24/ Section 5/ 5.2 32 CH Network Video Recorder	Video Compression: H.264, H. 265	Request to consider & add H.265+ also, which is latest compression technology	Please See the changes in the Corrigendum

Sr. No.	RFP Reference/Page No./Clause No. /Section No.	RFP Clause / Specifications	Query / Clarification / Suggestions from the Venders	Responses of GIL
10	Page No24/ Section 5/ 5.2 32 CH Network Video Recorder	2 no. of RS-485	Request to keep 1 RS-485 port as now a days RS-485 port is not used due to controlling possible through LAN cable only	Please See the changes in the Corrigendum
11	Page No 24, 5.2 32 CH Network Video Recorder	Support 300 Mbps of incoming Bandwidth	250 Mbps is sufficient for 32 IP cameras and standard bandwidth as per industrial standard for 32 ch NVR , Hence request to modify the clause as "Support 250 Mbps of incoming Bandwidth "	Please See the changes in the Corrigendum
12	Page No 24/Section 5/ 5.2 32 CH Network Video Recorder	Interface: 3 USB, 2 HDMI, 1 VGA , 8 SATA, 2 RS-485, 1 RS-232, 16 CH Alarm in, 4 CH Alarm out, 1 CH Audio In, 1 CH Audio out, Should support Network storage and backup	16 ch Alarm Input is not the standard range for Alarm Input, Request to Modify the clause as 8ch Alarm in as per industrial standard for 32 ch NVR All IP PTZ cameras and keyboards are Network based hence RS-232 will not be required in NVR . Request to remove 1 RS 232 port	Please See the changes in the Corrigendum